

CryptoRights Foundation, Inc. (501c3)
PO Box 708, Cobb, CA, 95426

+1 415 333 3003
<https://ciphr.org/build>

WINDOWS: (23) Windows total

The project's 'standard' window (*) is a:

3030 (3'x3') Casement Window; double-pane, gas-filled, hinged.
Hinges are viewed from inside.

.....
Main Room:

• East + South Walls:

Lower;

(5) 3030 Casements; 2/fixed, 3/open/crank; right-hinge.

Upper;

(5) 3030 Casements; 5/fixed.

◇ East Wall/Clerestory;

(3) 1030 Casements; open/pole; top-hinge.

† West Wall;

(2) 2040 Casements; 1/fixed, 1/opening; left-hinge.

.....
• East/Kitchen;
(2) 3030 Double-Hung.

.....
• West/Bath;
(1) 3030 Casement; open/crank; left hinge.

.....
• East+North+West/Storage Loft;
(5) 3030 Casements; open/crank; 2/top-,3/left-hinge.

DOORS: (3) Doors Total

Entry; 36"-Wide Solid Wood Door; No Glass; Kickplates.
Right Hinge (from inside); Opens In;

Kitchen; 32"-Wide "Dutch" Door;
Left Hinge (from inside); Opens In;
Bottom/Solid; Kickplates;
Top/ Glass/4 Lights; 2x-Pane.

Loft; 30"-W;
Top/ Glass/4 Lights; 2x-Pane.